


Technical Data

in detail



Technical data	HF 300.I	HF 450.I	HF 600.I	HF 800.I	HF 1000.I	HF 1300.I
Inverting Filter Centrifuges						
Basket diameter (mm)	300	450	600	800	1000	1300
Filtering surface area (m²)	0,1	0,31	0,41	0,85	1,26	2,0
Nominal volume (ltr.)	6,5	26	52	120	200	350
Speed max. (1/min)	3000	2300	1940	1600	1270	1000
Spinning speed (× g)	1500	1322	1255	1138	900	722
Weight (kg)	1400	3250	3500	6200	8900	10700
Length (mm) <b>A</b>	2025	3095	3095	4080	5090	5950
Width closed (mm)	930	1605	1605	2065	2290	2600
Width opened (mm)	1170	2450	2450	3190	3735	4600
Height (mm) <b>B</b>	1065	1735	1735	1900	2550	3300

Inverting Filter Centrifuge HF

After Sales Service

Product Support

**Wearing and spare parts**  
Worldwide delivery ex stock and web-shop for orders

**Engineering support**  
Solutions for all mechanical, control and process engineering questions

**Repairs**  
Worldwide on-site within 24/7

Solution Support

**Conversions and retrofits**  
ATEX upgrades, cGMP upgrades, retrofitting of pressurised filling pipes, controllers, displays, drive system replacements, safety services

**Maintenance contracts**  
After sales service with individually specified scope

**Process engineering optimisation**  
Optimisation of comprehensive process engineering processes

Sales Support

**Installation / commissioning**  
On-site installation  
Mechanical and electrical testing, test runs

**Training**  
Staff training on operation, control and trouble-shooting

**Maintenance**  
Remote maintenance and on-site maintenance

Business Support

**Used machines**  
Partial or full refurbishing of used machines from all manufacturers

**Rental and pilot systems**  
for rapid compensation of broken down systems and basic tests

**Financing**  
Hire-purchase, leasing



Service to us means doing everything so that your centrifuge, dryer, mixer and fittings will work reliably and safely for producing an optimum product.

We feel responsible for our machines and systems - from initial consulting through delivery, installation and maintenance up to the end of the entire life cycle.

Through the partnership-like cooperation with our customers around the world we jointly provide top performance, contributing significantly to your success.

In a world in which markets and people move together even more closely, our group of companies can assist you by providing top quality products, services and staff.

As one of the international leading vendors we endeavour to be as close as possible to our customers thereby ensuring utmost satisfaction.

Firmly embedded on all levels of our company, we endeavour to provide high quality, accuracy and reliability every day.

Our staff is continually trained so as to meet all aspects of the high process engineering and statutory requirements of the pharmaceutical, chemistry and metal industries.