


109008



DWG. NO. 24-2189		REV. A	1	
REVISIONS				
ZONE	REV.	DESCRIPTION	DATE	APPROVED
A		ORIGINAL	10/5/99	ETM

BILL OF MATERIAL:

ITEM NO.	FIND NO.	DESCRIPTION
1.	001	VACUUM PUMP EC-125L
2.	2CA	MOTOR 7.5 HP TFEC-SD
3.	2XC	SEPARATOR
4.	3FB	STRAINER RECIRC. LINE
5.	3EA	BASE
6.	2LB	HEAT EXCHANGER
7.	3FF	STRAINER - MAKE UP
8.	3AC	LEVEL SWITCH - MAKE UP
9.	2HA	GAUGE GLASS
10.	2VF	ORIFICE UNION
11.	2BA	COUPLING
12.	2BB	FLOW CONTROL VALVE - MAKE UP
13.	2BC	SOLENOID VALVE - MAKE UP
14.	2BD	BYPASS VALVE - MAKE UP
15.	2BE	DRAIN VALVE

50.	3AA	INLET ISOLATION VALVE
51.	27A	INLET CHECK VALVE
52.	2JK	VACUUM GAUGE W/COCK
53.	3BA	RELIEF VALVE

NOTES:

- REFER TO ENGINEERING DATA SHEET FOR CERTIFICATION AND ITEMS SPECIFICALLY FURNISHED FOR THIS ORDER.
- 1/4 MESH S.S.T.L. TEMPORARY SCREEN FOR PUMP INLET SUPPLIED BY NASH ENGRG. CO. FOR PROTECTION FROM FOREIGN MATERIAL DURING START-UP PERIOD.
- FOUNDATION BOLTS ARE NOT FURNISHED.
- PUMP PIPE THREAD CONNECTIONS ARE ANSI B1.20.1.
- FOR INSTALLATION AND OPERATION SEE INSTRUCTION MANUAL.
- SOLIDLY GROUND UNIT. DO NOT USE PIPING SYSTEM FOR GROUND.
- BASE IS NOT DESIGNED TO BE SELF-SUPPORTING AND MUST BE GROUTED TO FORM A RIGID SUPPORT UNDER FULL AREA OF BASE.
- INLET PIPING IS NOT FURNISHED WITH THE STANDARD PACKAGE. AN ELBOW IS FURNISHED WHEN ITEMS 50 AND/OR 51 ARE ORDERED. A TEE REPLACES THE ELBOW WHEN ITEM 53 IS ORDERED.



DUPONT-DANISCO PO# DDCE-0122
EQUIP. NO. P9000-3 STILLAGE VACUUM PUMP

THIS DRAWING CONTAINS PROPRIETARY INFORMATION OF THE NASH ENGINEERING COMPANY, TRUMBULL, CT. 06611-1330, USA. PERMISSION IS HEREBY GIVEN TO ANY NASH CUSTOMER TO USE AND REPRODUCE THE INFORMATION CONTAINED HEREIN IN CONNECTION WITH THE CUSTOMER'S USE OF ANY NASH PRODUCT. NO OTHER USE MAY BE MADE OF THIS INFORMATION WITHOUT WRITTEN PERMISSION FROM NASH.				ENR R. M.	DATE 10/5/99	NASH ENGINEERING COMPANY TRUMBULL, CONN. 06611-1330
- UNLESS OTHERWISE NOTED -				CHKR ETM	10/13/99	
DIMENSIONAL UNITS ARE: INCHES				APFD OSH CHB	10/13/99	INSTALLATION EC-125L DELTA PAK RECIRCULATED SEAL DIRECT DRIVE
- TOLERANCES -				APFD DHR EHN	10/13/99	
GENERAL	MOUNTING HOLE LOCATIONS	PIPE CONNECTION LOCATIONS		APFD GA	SIZE FROM NO.	DWG NO.
± .13	± .06	≤ 2" NPS	> 2" NPS	PROJECTION	D 42280	24-2189
					SCALE NONE	REV 1



DETAIL X ITEM 53 WHEN ORDERED (SEE NOTE 8)

VIEWED AT THIS END DIRECTION OF ROTATION IS COUNTER-CLOCKWISE
SEPARATOR NOT SHOWN IN THIS VIEW FOR CLARITY

DWG NO	24-1938	SH	REV	1
REVISIONS				
ZONE	REV	DESCRIPTION	DATE	APPROVED
A		ORIGINAL	3/27/98	RAL
B		REVISED DIMENSIONS (ECN 1133U98)	5/19/98	RAL
C		REVISED DIMENSIONS (ECN 1145U98)	6/28/98	RAL
D		EC-125L WAS 184TC (ECN 1104U99)	4/13/99	FSM



ITEM NO.	DESCRIPTION
1	VACUUM PUMP
2	MOTOR (IF SUPPLIED)
3	COUPLING (IF SUPPLIED)



- NOTES:
- REFER TO ENGINEERING DATA SHEET FOR CERTIFICATION AND ITEMS SPECIFICALLY FURNISHED FOR THIS ORDER.
 - STAINLESS STEEL TEMPORARY SCREEN FOR PUMP INLET WILL BE SUPPLIED BY NASH ENGINEERING CO. FOR PROTECTION FROM FOREIGN MATERIAL DURING START-UP PERIOD. TWO SCREENS (1/4" & NO. 30 MESH) WILL BE SUPPLIED WITH STAINLESS STEEL PUMPS. THE NO. 30 MESH SCREEN SHOULD BE INSTALLED ON THE UPSTREAM SIDE OF THE 1/4" MESH SCREEN.
 - FOUNDATION BOLTS ARE NOT FURNISHED.
 - 4A. ALL IRON PUMP FLANGES ARE FLAT FACE AND CONFORM TO ANSI CLASS 125 BOLT PATTERNS. BOLT HOLES STRADDLE CENTERLINES.
 - 4B. ALL ST. STL. PUMP FLANGES ARE RAISED FACE AND CONFORM TO ANSI CLASS 150 BOLT PATTERNS. BOLT HOLES STRADDLE CENTERLINES.
 - PUMP PIPE THREAD CONNECTIONS ARE ANSI B1.20.1.
 - FOR INSTALLATION AND OPERATION SEE INSTRUCTION BULLETINS.
 - SOLIDLY GROUND UNIT. DO NOT USE PIPING SYSTEM FOR GROUND.
 - DIMENSION "A" IS FOR REFERENCE ONLY BASED ON STANDARD TEFC MOTORS.
 - DRAWING NOT CERTIFIED UNLESS STAMPED.

PUMP SIZE	NEMA MTR FRAME	A	B	C	D	E	F	G	H	I	J (C.I.)	J (S.S.)	K	L	M	N	P	P ₁	Q	R	S	T	U	V	W-MM	X-MM	Y-MM	Z-MM	AA	BB	CC
EC-90L	184TC	34.63	7.25	7.00	21.32	1.00	3.55	7.10	11.02	.55	12.90	13.31	6.30	1.06	13.00	8.27	2.56	1.38	2.30	2.36	8.27	9.92	2.95	4.13	7.0	31.0	8.0	28.0 (K6)	1-1/2	1-1/2	3/8
EC-125L	213TC	35.37	8.00	7.00	22.06	1.00	3.55	7.10	11.02	.55	12.90	13.31	6.30	1.06	13.00	8.27	2.56	1.38	2.30	2.36	8.27	9.92	2.95	4.13	7.0	31.0	8.0	28.0 (K6)	1-1/2	1-1/2	3/8
EC-150L	213TC	36.62	8.23	8.80	22.07	0.25	3.55	7.10	11.02	.55	12.90	13.31	6.30	1.06	13.00	8.27	2.56	1.38	2.30	2.36	8.27	9.92	2.95	4.13	7.0	31.0	8.0	28.0 (K6)	1-1/2	1-1/2	3/8
EC-250L	215TC	42.18	8.90	8.80	27.80	1.00	3.94	7.88	15.60	.71	16.14	16.14	7.68	1.30	15.37	12.40	2.76	1.60	2.50	3.00	9.84	11.80	3.75	4.92	8.0	41.0	10.0	38.0 (J6)	3	3	1/2
EC-320L	254TC	48.44	10.15	10.10	28.94	0.25	3.94	7.88	15.60	.71	16.14	16.14	7.68	1.30	15.37	12.40	2.76	1.60	2.50	3.00	9.84	11.80	3.75	4.92	8.0	41.0	10.0	38.0 (J6)	3	3	1/2
EC-450L	256TC	50.25	11.92	10.10	30.70	0.25	3.94	7.88	15.60	.71	16.14	16.14	7.68	1.30	15.37	12.40	2.76	1.60	2.50	3.00	9.84	11.80	3.75	4.92	8.0	41.0	10.0	38.0 (J6)	3	3	1/2

THIS DRAWING CONTAINS PROPRIETARY INFORMATION OF THE NASH ENGINEERING COMPANY TRUMBULL, CT 06611-1330, USA. PERMISSION IS HEREBY GIVEN TO ANY NASH CUSTOMER TO USE AND REPRODUCE THE INFORMATION CONTAINED HEREIN IN CONNECTION WITH THE CUSTOMER'S USE OF ANY NASH PRODUCT. NO OTHER USE MAY BE MADE OF THIS INFORMATION WITHOUT WRITTEN PERMISSION FROM NASH.

- UNLESS OTHERWISE NOTED -
 DIMENSIONAL UNITS ARE: INCHES UNLESS OTHERWISE NOTED
 - TOLERANCES -

GENERAL	MOUNTING HOLE LOCATIONS	PIPE CONNECTION LOCATIONS	LOCATIONS > 2" NPS	LOCATIONS > 7" NPS
± .13	± .06	± .13	± .06	

DRAWN	R.M.	DATE	3/27/98
CHECKED	RAL	DATE	3/31/98
APPROVED DESIGN	LJL	DATE	3/31/98
APPROVED FOR FABRICATION	RAL	DATE	3/31/98
APPROVED FOR ASSEMBLY		DATE	

NASH ENGINEERING COMPANY
 TRUMBULL, CONNECTICUT 06611-1330

INSTL. DWG. VACUUM PUMP MODELS EC-90L, 125L, 150L, 250L, 320L, 450L

SHEET NO.	42280	DWG. NO.	24-1938
SCALE		SHEET	1 OF 1

EN 1357-001


PERFORMANCE: EC125 VACUUM PUMP

30 Hg Barometer , 60 Deg F Seal Water

REV C - 1999

Performance to HEI Standard

VOLUME - AT THE VACUUM (ACFM)



HORSEPOWER (HP)



Vacuum (in. Hg vac)

	Finder Pompe SpA Via Bergamo, 65 23807Merate (Lc) Italy tel (+39)(39)9982.1 fax(+39)(39)599267	CERTIFICATO FUNZIONALE PERFORMANCE CERTIFICATE EN 10204 2.2	Pag. 1/1 CFC 0702304-1

Cliente Customer	Gardner Denver Nash	Descrizione Description	EC 125L	Procedura Procedure	PCQ PF10
N. dell'ordine Order no.	443477	Posizione No. Item		Piano Controllo Control Plan	
Commessa N. Job no.	0702304	N. di Serie / Codice Serial no.	070911/S/57	Pagina / fase Sheet / step	

Collaudo Funzionale Performance Test - PNEUROP 6612

Dati Pompa Pump Data								Dati Contrattuali della pompa Pump performance required				
		N	1	2	3	4	5	Portata	Capacity	Qc	m³/h	
Dati Riportati Data with	Volt	V	400	400	400	400	400	Pressione di Aspirazione	Suction Pressure	P1	mbar	
	ng	n.	1750	1750	1750	1750	1750	T. Liquido Servizio	Service Liquid temp.	TLg	°C	
		m bar	33	60	200	400	800	T. Liquido aspirazione	Suction Liquid temp.	T1g	°C	
		mm Hg	25	45	150	300	600	Giri	RPM	ng	n.	
ng	1750	Qc	m³/h	50,0	90,0	115,5	121,0	124,0	Pot. Assorbita	Absorbed power	Nc	Kw
TLg	15	Nc	Kw	3,05	3,45	3,77	3,90	3,90	Pot. Motore	Motor Power	Nm	Kw
T1g	20											



P1 (m bar)

Visivo/Dimensionale Visual/Dimensional	Hydrotest		Materiali Materials (ASTM)										
	ANSI/Hi		Corpo Casing	A 278 C 250		Girante Impeller		A 351CF8M		Albero Shaft		A 276 T.420	
	PCQ HT 02				C (%)	Mn (%)	Cr (%)	Ni (%)	Mo (%)	Si (%)	Rm (Mpa)	Rp (Mpa)	
Conforme al disegno Conform to drawing	Minuti Minutes	Bar	A 278 C 250								≥ 250		
CATALOGUE	5	5	A 351CF8M	≤ 0,06	≤ 1,5	≤ 0,04	≤ 0,04	18+21	9+12		≥ 485	≥ 205	
			A 276 T.420	≤ 0,5	≤ 1	12+14							

Si certifica che la totalità dei materiali e servizi, richiesti a fronte dell'ordine in oggetto, sono conformi in ogni parte alle specifiche, disegni e prescrizioni contrattuali.
 Si certifica inoltre che sono stati verificati e sottoposti alle prove di conformità, alle condizioni ed esigenze dell'ordine con esito positivo.
 We hereby certify that all materials and services required against the above mentioned order fully comply with specifications, drawings and contract recommendations.
 We also certify that all materials have been checked and submitted to internal test with positive results.

Data Date	18,09,2009	Eseguito Da Performed by	[Signature]	Approvato Da Approved by	[Signature]	Risultati Results Soddisfacente, Conforme alla procedura Satisfactory, Conform to procedure
------------------	------------	---------------------------------	-------------	---------------------------------	-------------	---