



Customer Document title:

Flowserve Construction Data Sheet

Flowserve Document title: **Flowserve Construction Data Sheet**Flowserve Document No.: **1400944-013-5009-01**Document Revision No.: **0**Flowserve Order No.: **1400944**Flowserve Serial No.: **1400944CHP013A/D**Pump Type/Size: **MARK 3 STANDARD / 2K4X3-10RV**Quantity: **4**Customer Name: **DESMET BALLESTRA NORTH AMERICA**

PROJECT - WORPAR

ITEM NBR - PW582D.1/1-PW582D.2/1

PW582D.2/1-PW582D.2/2

eB NBR - 100212964.000

DATE - 22.10.2021

Customer Tag No: **DESMET TAG#: PW582D.1/1, CUSTOMER TAG#: 19-P-773A, DESMET TAG#: PW582D.1/2, CUSTOMER TAG#: 19-P-773B, DESMET TAG#: PW582D.2/1, CUSTOMER TAG#: 19-P-873A, DESMET TAG#: PW582D.2/2, CUSTOMER TAG#: 19-P-873B**

Customer PO No.: **28493**End User: **DESMET BALLESTRA NORTH AMERICA**

Please complete and return:

Document Reviewed by:

Document Reviewed date:

- ☐ **APPROVED. NO ACTION REQUIRED**
☐ **APPROVED. RE-SUBMIT AS FINAL**
☐ **APPROVED WITH COMMENTS. DOCUMENT WILL BE MODIFIED AND RESUBMITTED AS FINAL**
☐ **REJECTED. CORRECT AND RE-SUBMIT FOR APPROVAL**
☐ **FOR INFORMATION. REVIEW NOT REQUIRED**
☐ **AS-BUILT**

- Return any documents sent for review with your comments by the stated return date. All documents not returned two weeks after requested Return date will be considered Approved, no action.
- Purchaser's comments and/or corrections within the scope of contract will be made on the first completed document submitted by Flowserve Corp. and returned.
- Corrections, alterations, additions and/or modifications outside scope of contract or made after first submittal may require an additional engineering service charge.
- Items conditionally approved or with deferred approval by purchaser must be specifically stated otherwise delivery may be affected.

Rev	Revision Description	Released	Release Date
	Internal Only		14-Sep-21

Customer	: DESMET PROCESS & TECHNOLO...	Pump / Stages	: 2K4x3-10RV M3 ST / 1
Customer reference	: WORPAR	Based on curve no.	: MIII7901FV
Item number	: PW582D.1/1, 1/2, 2/1, 2/2	Flowserve reference	: 1989206898
Service	: Oil Collecting Tank Disch.	Date	: August 26, 2021

Construction					Driver Information	
Nozzles	Size	Rating	Face	Position	Manufacturer	: WEG
Suction	4.00	150#	FF	End	Power	: 60.0 hp / 44.7 kW
Discharge	3.00	150#	FF	Top	Service factor (requested / actual)	: 1.15 / 1.15
Casing mounting : Foot					Synchronous speed	: 3,600 rpm
Casing split : Radial					Orientation / Mounting	: Horizontal / Foot
Impeller type : Reverse Vane					Driver type	: NEMA
Bearing type (radial) : Sgl Row					Frame-size / material	: 364TS / CAST IRON
Bearing number (radial) : 6310-C3					Enclosure	: IEEE-841
Bearing type (thrust) : Dbl Row					Hazardous area class	: -
Bearing number (thrust) : 5310-AHC3					Explosion 'T' rating	: -
Bearing lubrication : Flood					Volts / Phase / Hz	: 460 / 3 / 60 Hz
Rotation (view from driver) : CW per Hyd. Institute					Amps-full load/locked rotor	: 66.80 A / 427.00 A
Materials					Motor starting	: Direct on line (DOL)
Casing : 316SS (D4/CF8M)					Insulation	: F
Impeller : 316SS (D4/CF-8M)					Temperature rise	: -
Seal chamber : FML Box / (316SS)					Bearings	: Ball
Shaft : 316 SS					Lubrication	: Grease
Sleeve : No Sleeve					Motor mounted by	: Flowserve
Baseplate, Coupling and Guard					Sound Pressure (dBA @ 1.0 m)	
Baseplate type : Type D Reinforced					Driver, expected	: 83.0 dBA
Baseplate material : Steel					Pump & driver, estimated	: 86.0 dBA
Baseplate size : 264 Baseplate					Seal Information	
Coupling manufacturer : Rexnord					Arrangement	: Sgl Int O-Ring
Coupling size : Thomas 726 Std/XL					Size	: 1.875
Coupling / Shaft guard : Aluminum (Non-Spark)					Manufacturer / Type	: Flowserve / ISC2 Pusher
Shaft / seal guard : None Supplied					Material code (Man'f/API)	: C2CPX----ECXV- / BSTFN
Weights (Approx.)					Internal neck bushing	: Not Available
Bareshaft pump (net) : 225.0 lb					Gland	
Baseplate (net) : 442.0 lb					Gland material	: 316SS
Driver (net) : 807.0 lb					Flush	: .375" NPT
Shipping gross weight/volume : 1,695.1 lb / 38,526 cu.in					Vent	: .375" NPT
Testing					Drain	: .375" NPT
Hydrostatic test : Non witnessed					Auxiliary seal device	: Carbon Bushing
Performance test : Non witnessed					Piping	
NPSH test : None					Seal flush plan	: Plan 03
Paint and Package					Seal flush construction	: -
Pump paint : Epoxy Primer & Topcoat					Seal flush material	: -
Base grout surface prep : Flowserve St'd D14-3					Aux seal flush plan	: Plan 61
Shipment type : Domestic					Aux seal flush construction	: Not supplied
					Aux seal flush material	: Not supplied
Notes						
-						
ANSI 3A w/site, magnetic drain plug						
Casing w/1/2" Plugged Drain (NPT)						
-						
-						
XSD Drawing No. 0000AMK3SXX2KXXFTRVSSMSFM						