

QTY	MAKE FROM	MATL	WT		QTY	SYMBOL	DESCRIPTION	PT
			ROUGH	FIN.				
#	#	#	#	#	#	C. 0261 44 B 500	NAME PLATE ASS'Y	#
1	5.4011.102	#	#	#	#	#	NAME PLATE	001
		#	#	#	4	0.0278.599	SCREW M4X10	002

002

4 gaten ϕ 5

001

CENTRIFUGAL
COMPRESSOR

**DELAVAL
STORK**

DELAVAL-STORK V.O.F.
HENGELO
THE NETHERLANDS

NORMAL CAPACITY

258800 KG/HR

MAX. CONT. SPEED

2986 RPM

CASING DESIGN PRESS.

SUCT. 24 BARG
DISCH. 24 BARG

CASING DESIGN TEMP.

150 °C

FIRST CRITICAL SPEED

RPM. *

SHAFT TORQUE LIMIT

3000 KW

SIZE & TYPE

PV. 52

YEAR OF MANUFACTURE

1981 - 1982

SERIAL No.

LC. 0261

PURCHASER

CJB / GPSA - GREECE

PURCHASER'S No.

4110/A/4/30/01

ITEM No.

C. 1301

NOT:

* OVERNEMEN UIT TESTPROTOCOL/
WILL BE TAKEN FROM TESTPROTOCOL.

CHG	ZONE	ALTERATIONS	DATE	BY	CHK	WHY	BEDR
0	1	2	3	4	5	6	7
CERT. FOR CONSTR: <i>C. Kamp</i>							
SEE A0621.2 FOR TOL'S ETC. NOT SPECIFIED							
FIRST ORDER: LC. 0261				REF. DWG.: C-024044 B 500			
HENGELO (OV)				PROJ. METHOD:			
NETHERLANDS							
TITLE: NAME PLATE							
DRAWN: P.W.		JAN. 82		SCALE: 1:1			
CHK: P.W.		8 FEBR. 82		SHEETNO. 1		OF 1	
ISSUED: P.W.		1/2-82		NO.: C. 0261 44 B 500			
PVB.		GERTEK					
COPYRIGHT IS RESERVED BY LAW DLS-EC. 2811							

Voor het bevestigen schroeven art.nr. 0.0278.599 gebruiken.

Materiaal : Stainless steel 18.8 2 mm dik.

Uitvoering: Letters en figuren 0,4 mm diep graveren en opvullen met zwarte olie- en alcoholbestendige verf.

Zwarte gedeelte van het embleem 0,4 mm diep uitfrezen en schilderen met oranje (RAL Nr. 2004) olie- en alcoholbestendige verf.